

RENTAL - SALES - PARTS & SERVICE Tel: (888) 337-BIGGE or (510) 638-8100 Web: www.bigge.com

### STINGER 70100 | Boom Truck Crane



### FEATURES

- 70,000 lb (31 752 kg) maximum lifting capacity
- 110' (33.53 m) maximum sheave height
- 163' (49.68 m) maximum sheave height with 30.5-55' (9.30-16.76 m) jib
- 30.5-100' (9.30-30.48 m) four-section full power fully synchronized boom
- Exclusive color coded boom and load charts
- Easy-to-install optional 30.5' (9.30 m) one stage or 30.5-55' (9.30-16.76 m) two stage telescoping jib, man baskets or work platform increase job capacities

- Electronic Load Moment Indicator and anti-two-block device standard with internal cable
- Externally located planetary rotation drive for easy accessibility for maintenance
- 2-speed planetary winch has 12,900 lb (5 851 kg) maximum permissible 1 part line, 45,400 lb (20 593 kg) breaking strength, 196 ft/min (60 m/min) maximum line speed
- Dual control station with direct mechanically controlled hydraulic system
- > 90 gal (342 L) capacity hydraulic tank

BİGGE

This information is for reference use only. Operators manual should be consulted and adhered to. Please contact Bigge Crane and Rigging Co. at 888-337-BIGGE or email info@bigge.com for further information.






### **BT MODEL**

### LOAD RATINGS CAUTION Do not use this specification sheet as a load rating chart. The format is not consistent with the machine chart and may be subject to change.

BOOM I	LENGTH					Maximu	m Load Cl	hart in pou	ınds (lbs) v	with fully e	xtended c	utrigger	
	30.	5 FT	44	FT	58 FT		-T 72 FT		86 FT		100 FT		
operating Radius (FT)	LOADED BOOM ANGLE (DEG)	Load Rating (LB)	LOADED BOOM ANGLE (DEG)	LOAD Rating (LB)	LOADED BOOM ANGLE (DEG)	Load Rating (LB)	LOADED BOOM ANGLE (DEG)	LOAD Rating (LB)	LOADED BOOM ANGLE (DEG)	LOAD Rating (LB)	LOADED BOOM ANGLE (DEG)	LOAD Rating (LB)	AREA OF OPERATION
5	78	70,000*											IN SHADED AREA
8	72	60,800*				t							WITHOUT
10	68	44,800*	75	31,300*									OPTIONAL FRONT
12	64	40,000*	72	31,700*	77	31,100*		1					STABILIZER
15	58	33,200*	68	31,600*	74	30,500*	77	27,600*					
20	45	24,400*	61	24,500*	68	23,600*	73	21,200*	76	19,000*			
25	29	18,300*	53	19,100*	63	19,100*	69	17,200*	72	15,300*	75	12,100*	
30			44	15,000*	57	15,400*	64	14,400*	69	12,900*	72	10,500*	
35			34	11,400	51	11,800	60	12,000	65	11,100*	69	9,100*	
40			18	8,700	44	9,300	55	9,400	61	9,500	66	7,000*	
45	-				36	7,300	50	7,600	57	7,700	62	6,000*	
50	NOTE: S	TRUCTURAL S	TRENGTH RAT	TINGS IN	27	5,800	44	6,100	53	6,200	59	5,100*	
55	CHART /	ARE INDICATED	WIH AN ASTI	ERISK *	11	4,600	38	5,000	49	5,100	56	4,500*	
60	-						31	4,000	44	4,200	52	3,900*	*
65							22	3,200	39	3,400	48	3,400*	
70								1	34	2,800	44	2,900	
75						1		1	27	2,200	40	2,400	
80									18	1,700	35	1,900	Deductions from rate loads for load handling
85				_		· · · · · · · · · · · · · · · · · · ·		1			30	1,500	devices BT
90		1						1.000			24	1,100	
95								1.000			15	800	Overhaul Ball 200 lbs
STOWE	D JIB DE		NS (POL	JNDS)									1 Sheave Load Block 225-550 lbs
900 700 500 400 335 300 <sup>2</sup> Sheav					2 Sheave Load Block 300-650 lbs								

JIB CAPACITIES	<b>5 FOR ALL</b>	BOOM	LENGTHS	VERIFY OPERA	TIONAL MODE SET	TING ON LMI DISPL	AY BEFORE LIFTIN	G WITH JIB
Loaded Boom Angle	50°	55°	60°	65°	70°	75°	78°	80°
Retracted 30.5 ft Jib	800	1,400	2,300	3,300	4,000	5,300	6,000	6,450
Extended 55 ft Jib	700	1,050	1,700	2,300	3,000	3,500	3,500	3,500

### RANGE DIAGRAM (30.5 - 100 FT BOOM)



### **GENERAL NOTES**

- 1. The operator must read and understand the Owner's Manual before operating this crane.
- Positioning or operation of crane beyond areas shown on this chart is not intended or approved except where specified in Owner's Manual.
- 3. Loaded boom angles at specified boom lengths give only an approximation of the operating radius. The boom angle before loading should be greater to account for deflections. Do not exceed the operating radius for rated loads.
- Use rating of next longer boom for boom lengths not shown. Use rating of next greater radius for load radii not shown.
   Boom must be fully retracted when jib is erected before lowering below minimum angle. Retracted jib has no lifting capacity below a 50° boom angle.
- Use rating of next lower boom angle for boom angles not shown on jib load rating chart.
- 7. Lifting off the main boom point while the swing around jib is erected is not intended or approved.
- Do not lower boom into this area, as hydraulic pressure will not allow raising the boom without retracting boom first.
   Crane load ratings on outriggers are based on freely suspended loads with the machine leveled and standing on a firm
- uniform supporting surface. No attempt shall be made to move a load horizontally on the ground in any direction. 10. Practical working loads depend on supporting surface, wind and other factors affecting stability such as hazardous
- surroundings, experience of personnel, and proper handling, must all be taken into account by the operator. 11. The maximum load which may be telescoped is limited by hydraulic pressure, boom angle, and boom lubrication. It is
- safe to attempt to telescope any load within the limits of the load rating chart. INFORMATION
- Deductions must be made from rated loads for stowed jib, optional attachments, hooks and loadblocks (see deduction chart). Weights of slings and other load handling devices shall be considered a part of the load.
- 2. Crane load ratings with outriggers are based on outriggers and stabilizers extended and set with all load removed from the carrier wheels.

3. Load ratings do not exceed 85% of tipping load. DEFINITIONS

- Operating radius is the horizontal distance from the axis of rotation to the center of the vertical hoist line or load hook with load suspended.
- Loaded boom angle as shown in the Load Ratings Chart is the included angle between the horizontal and longitudinal axes of the boom base after lifting rated load at rated radius.



🛕 BİGGE



### **RS MODEL**


LOAD RATINGS

Retracted 30.5 ft Jib

Extended 55 ft Jib

### CAUTION Do not use this specification sheet as a load rating chart. The format of data is not consistent with the machine chart and may be subject to change.

BOOM	LENGTH					Maximu	n Load Cł	nart in pou	nds (Ibs) v	with fully e	xtended o	utrigger		
	30.	5 FT	44	FT	58	FT	72	FT	86	6 FT	100	) FT		
operating Radius (FT)	LOADED BOOM ANGLE (DEG)	LOAD Rating (LB)	AREA OF OPE 360° Full Cap											
5	74	70,000*											Area of	duity
8	67	44,900*											Operation	
10	63	39,000*	72	31,100*										
12	59	34,400*	69	31,100*	74	31,100*								
15	52	29,190*	65	27,800*	71	26,700*	75	24,200*					- FIT	
20	38	22,300*	57	22,000*	66	21,200*	71	19,200*	74	17,000*				A
25	17	14,900*	49	18,000*	60	17,500*	67	16,000*	71	14,400*	73	12,100*	1.	1-
30			40	14,800*	54	14,700*	62	13,300*	67	12,000*	70	10,500*		
35			27	11,600	48	12,000	57	11,500*	63	10,300*	67	9,100*		- 1
40					41	9,200	53	9,400	59	9,100*	64	6,500*	/	- /
45	NOTE: ST	BUCTURAL ST	BENGTH BATH		32	7,200	47	7,400	55	7,500	61	5,600*		1
50		RE INDICATED			21	5,700	42	5,900	51	6,000	58	4,900*		/
55							35	4,700	47	4,900	54	4,200*		
60		-					27	3,800	42	3,900	50	3,600*		
65							16	3,000	37	3,200	47	3,100*		
70									31	2,500	42	2,600*	Deductions fro	am roto
75									23	2,000	38	2,100	loads for load	
80									12	1,500	33	1,600	devices BT	
85		-									27	1,200		
90											20	900	Overhaul Ball	200 lbs
95		-						1			7	600	1 Sheave Load Block	225-550 lbs
STOWE	D JIB DE	DUCTIO	NS (P <u>OL</u>										2 Sheave Load Block	300-650 lb
	9	00	70	00	50	00	40	00	3	35	3	00		
JIB C	APAC	ITIES	FOR	ALL E	воом	LEN	GTHS	VERIFY OF	PERATIONAL	MODE SETT	TING ON LMI	DISPLAY B	EFORE LIFTING WITH .	IIB
Loaded Bo	om Angle		50°		55°	6	Do	65°		70°	75°		78º 8	80°



800

700

1,400

1.050

2.300

1.700

### **GENERAL NOTES**

3.300

2.300

1. The operator must read and understand the Owner's Manual before operating this crane.

4,000

3.000

- Positioning or operation of crane beyond areas shown on this chart is not intended or approved except where specified in Owner's Manual.
- Loaded boom angles at specified boom lengths give only an approximation of the operating radius. The boom angle before loading should be greater to account for deflections. Do not exceed the operating radius for rated loads.

5,300

3.500

6,000

3.500

6.450

3,500

- Use rating of next longer boom for boom lengths not shown. Use rating of next greater radius for load radii not shown.
   Boom must be fully retracted when jib is erected before lowering below minimum angle. Retracted jib has no lifting capacity below a 50° boom angle.
- Use rating of next lower boom angle for boom angles not shown on jib load rating chart.
- 7. Lifting off the main boom point while the swing around jib is erected is not intended or approved
- Do not lower boom into this area, as hydraulic pressure will not allow raising the boom without retracting boom first.
   Crane load ratings on outriggers are based on freely suspended loads with the machine leveled and standing on a firm
- uniform supporting surface. No attempt shall be made to move a load horizontally on the ground in any direction. 10. Practical working loads depend on supporting surface, wind and other factors affecting stability such as hazardous
- surroundings, experience of personnel, and proper handling, must all be taken into account by the operator. 11. The maximum load which may be telescoped is limited by hydraulic pressure, boom angle, and boom lubrication. It is safe to attempt to telescope any load within the limits of the load rating chart.
- INFORMATION
- 1. Deductions must be made from rated loads for stowed jib, optional attachments, hooks and loadblocks (see deduction chart). Weights of slings and other load handling devices shall be considered a part of the load.
- 2. Crane load ratings with outriggers are based on outriggers and stabilizers extended and set with all load removed from the carrier wheels.
- 3. Load ratings do not exceed 85% of tipping load. DEFINITIONS
- Operating radius is the horizontal distance from the axis of rotation to the center of the vertical hoist line or load hook with load suspended.
- Loaded boom angle as shown in the Load Ratings Chart is the included angle between the horizontal and longitudinal axes of the boom base after lifting rated load at rated radius.








### **BT MODEL**

WINCH DATA							
		1 Part Line	2 Part Line	3 Part Line	4 Part Line	5 Part Line	6 Part Line
		OVERHAUL	ONE SHEAVE LIGAD BLOCK	ONE SHEAVE LOAD BLOCK	TWO SHEAVE LOAD BLOCK	TWO SHEAVE LOAD BLOCK	THREE SHEAVE LOAD BLOCK
Winch	Cable	Lift and	Lift and	Lift and	Lift and	Lift and	Lift and
	Supplied	Speed	Speed	Speed	Speed	Speed	Speed
Standard	5/8" Diam	12,971 lb	25,942 lb	38,913 lb	51,844 lb	64,855 lb	70,000 lb
Stationary	IWRC XXIP	196 fpm	98 fpm	65 fpm	49 fpm	39.2 fpm	32.7 fpm
Winch	5/8" Diam	9080 lb	18,160 lb	27,240 lb	36,320 lb	45,400 lb	54,480 lb
	Rotation Resistant	196 fpm	98 fpm	65 fpm	49 fpm	39.2 fpm	32.7 fpm

### **2 MOUNTING CONFIGURATIONS**



### **CARRIER PROVIDED BY TEREX**

STINGER BT70100 - Behind Cab Mo	ounting Configuration
Manufacturer	Sterling LT7501 6 x 4 (60 000)
Standard Engine	Caterpillar C-7 7.2 L I-6
Standard Horsepower	300 hp @ 2,200 rpm
Standard Torque	860 lb. Ft. @ 1,440 rpm
Full Tank Capacity	120 gal (454 L)
Standard Transmission	Eaton Fuller RT-8908LL
Speed Standard Transmission	Manual 10-speed
<ul> <li>Max Speed Standard Transmission</li> </ul>	74 mph (120 km/h)
<ul> <li>Max Gradeability</li> </ul>	54%
Standard Transmission	
Optional Transmission	Allison
Speed Optional Transmission	Automatic 6-speeds
Max Speed Optional Transmission	74 mph (120 km/h)
Max Gradeability	17%
Optional Transmission	
<ul> <li>Gross Vehicle Weight Rating</li> </ul>	60,000 lb (27 210 kg)
Front Axle Weight Rating	20,000 lb (9 067 kg)
Rear Axle Weight Rating	40,000 lb (18 144 kg)
<ul> <li>Front Tires</li> </ul>	425/65R 22.5 Michelin XZY (20 ply)
Rear Tires	11R 22.5 Michelin XDE M/S (14 ply)
<ul> <li>Brakes</li> </ul>	Air, Hydraulic Anti-Lock System
<ul> <li>Exhaust Position</li> </ul>	Vertical Right Side


<b>BLOCK TYPI</b>	E
Overhaul Ball	Rating: 7.0 ton (6.3 mt
1 Sheave Block	Rating: 20 ton (18.1 m

I SHEAVE DIUCK	naling. 20 lun (10.1 ml)	
2 Sheave Block	Rating: 30 ton (27.2 mt)	
3 Sheave Block	Rating: 35 ton (31.7 mt)	

### CAUTION

Overload and anti-two-block systems must be in good operating condition before operating crane. Refer to Owners Manual.

Keep at least 3 wraps of loadline on drum at all times. Use only 5/8" diameter cable with 45,400 lb breaking strength on this machine.



### **INCLUDED OPTIONS**

- Dual Fuel Tanks (120 gal-454L)
- Power steering
- Electric Horn
- Factory A/C
- Power Port (Cigar lighter)
- AM/FM Radio w/ Clock
- Dual West Coast Stainless Rear View Mirrors
- Standard Factory Warranty

### **CHASSIS RECOMMENDATIONS**

STINGER BT70100 - Behind Cab Mo	ounting Configuration
Combined Axle Weight Rating	60,000 lb (27 210 kg)
Front Axle Weight Rating	20,000 lb (9 067 kg)
Rear Axle Weight Rating	40,000 lb (18 144 kg)
Wheel base	261" (6.62 m)
Cab to Axle	192" (4.87 m)
<ul> <li>Afterframe</li> </ul>	114" (2.90 m)
Frame Section Modulus	30.0 in <sup>3</sup> (491 cm <sup>3</sup> )
RBM per Frame Rail	3,300,000 in/lb (38 020 kg/m)
Frame Height (Unloaded)	40" (7.62 m)
Exhaust Position	Vertical Right Side






### **RS MODEL**

WIN	WINCH DATA						
		1 Part Line	2 Part Line	3 Part Line	4 Part Line	5 Part Line	6 Part Line
		OVERHAUL	ONE SHEAVE LOAD BLOCK	ONE SHEAVE LOAD BLOCK	TWO SHEAVE LOAD BLOCK	TWO SHEAVE LOAD BLOCK	THREE SHEAVE LOAD BLOCK
Winch	Cable	Lift and	Lift and	Lift and	Lift and	Lift and	Lift and
	Supplied	Speed	Speed	Speed	Speed	Speed	Speed
Standard	5/8" Diam	12,971 lb	25,942 lb	38,913 lb	51,844 lb	64,855 lb	70,000 lb
Stationary	IWRC XXIP	196 fpm	98 fpm	65 fpm	49 fpm	39.2 fpm	32.7 fpm
Winch	5/8" Diam	9080 lb	18,160 lb	27,240 lb	36,320 lb	45,400 lb	54,480 lb
	Rotation Resistant	196 fpm	98 fpm	65 fpm	49 fpm	39.2 fpm	32.7 fpm

### **2 MOUNTING CONFIGURATIONS**



### **CARRIER PROVIDED BY TEREX**


STINGER RS70100 Riding Seat Mou	nting Configuration
Manufacturer	Sterling LT7501 6 x 4 (60 000)
Standard Engine	Caterpillar C-7 7.2 L I-6
Standard Horsepower	300 hp @ 2,200 rpm
Standard Torque	860 lb. Ft. @ 1,440 rpm
Full Tank Capacity	120 gal (454 L)
Standard Transmission	Eaton Fuller RT-8908LL
Speed Standard Transmission	Manual 10-speed
Max Speed Standard Transmission	74 mph (120 km/h)
Max Gradeability	54%
Standard Transmission	
Optional Transmission	Allison
Speed Optional Transmission	Automatic 6-speeds
Max Speed Optional Transmission	74 mph (120 km/h)
Max Gradeability	17%
Optional Transmission	
Gross Vehicle Weight Rating	60,000 lb (27 210 kg)
Front Axle Weight Rating Rating	20,000 lb (9 067 kg)
Rear Axle Weight Rating Rating	40,000 lb (18 144 kg)
Front Tires	425/65R 22.5 Michelin XZY (20 ply)
Rear Tires	11R 22.5 Michelin XDE M/S (14 ply)
Brakes	Air, Hydraulic Anti-Lock System
Exhaust Position	Vertical Right Side

Overhaul BallRating: 7.0 ton (6.3 mt)1 Sheave BlockRating: 20 ton (18.1 mt)	BLOCK TYPE				
1 Sheave Block Rating: 20 ton (18.1 mt)	) ton (6.3 mt)	Overhaul Ball			
	ton (18.1 mt)	1 Sheave Block			
2 Sheave Block Rating: 30 ton (27.2 mt)	ton (27.2 mt)	2 Sheave Block			
3 Sheave Block Rating: 35 ton (31.7 mt)	ton (31.7 mt)	3 Sheave Block			

### CAUTION

Overload and anti-two-block systems must be in good operating condition before operating crane. Refer to Owners Manual.

Keep at least 3 wraps of loadline on drum at all times. Use only 5/8" diameter cable with 45,400 lb. breaking strength on this machine.



### **INCLUDED OPTIONS**

- Dual Fuel Tanks (120 gal-454 L)
- Power steering
- Electric Horn
- Factory A/C
- Power Port (Cigar lighter)
- AM/FM Radio w/ Clock
- Dual West Coast Stainless Rear View Mirrors
- Standard Factory Warranty

### **CHASSIS RECOMMENDATIONS**

STINGER RS70100 Riding Seat Mo	ounting Configuration
Combined Axle Weight Rating	60,000 lb (27 210 kg)
Front Axle Weight Rating	20,000 lb (9 067 kg)
Rear Axle Weight Rating	40,000 lb (18 144 kg)
Wheel base	261" (6.62 m)
Cab to Axle	192" (4.87 m)
Afterframe	114" (2.90 m)
Frame Section Modulus	30.0 in <sup>3</sup> (491 cm <sup>3</sup> )
RBM per Frame Rail	3,300,000 in/lb (38 020 kg/m)
Frame Height (Unloaded)	40" (7.62 m)
Exhaust Position	Vertical Right Side


BİGGE 🛕

🛕 BİGGE



### **BT MODEL**

SPECIFICATIONS



### BOOM

30.5-100' (9.30-30.48 m) four-section full power fully synchronized boom. Patented keel boom design utilizes a keel shaped base plate combined with a deep, four plate boom section to optimize strength / rigidity-to-height ratio. Exclusive, patented color-coded boom and load charts allow the operator to easily determine boom extension, boom angle and load capacity. Maximum tip height with four-section 30.5-100' (9.30-30.48 m) boom is 110' (33.53 m). Maximum tip height with optional two-stage 30.5-55' (9.30-16.76 m) jib is 163' (49.68 m).

### **WINCH**

 Hydraulic winch with gear motor and planetary reduction gearing provides 2-speed operation. First layer rope pull is 15,000 lb (6 804 kg). Wire rope size is 5/8" (16 mm) with 45,400 lb (20 593 kg) breaking strength.

### **OPERATING SPEEDS**

 Mainframe / turret assembly planetary gear rotation provides 180° rotation (370° with optional front bumper outrigger). Swing rotation is 75 seconds. Boom up/down is 60/41 seconds and boom extend/retract is 108/50 seconds.

### **HYDRAULICS**

 Three-section pump allows the operator to perform simultaneous crane operations (winch, boom and swing). Capacities are 32, 17 and 8 gpm (122, 64 and 30 L/m). Hydraulic tank capacity is 90 gal (342 L).

### CONTROLS

 Fully proportional, excellent metering characteristics for precise boom movements. Independent outrigger controls allow the crane to be stable and level in rigorous working conditions. Load Moment Indication System has audio alarm and functional shut down when operator encounters an overload situation.

### **OUTRIGGERS**

- Front outriggers are Out & Down. The maximum width over main outrigger pads is 25' 6" (7.78 m).
- Rear outriggers are Out & Down. The maximum width over auxiliary outrigger pads is 17' 6" (5.33 m).

### SUBFRAME

 Single fabricated, closed-box style subframe yields greater strength and rigidity. Wheelbase for standard truck crane mounting configuration is 261" (6.62 m).

### **OPTIONS AND ACCESSORIES**

- Single and two-stage jibs
- Multi-part load blocks
- Main winch with 2 speed motor
- Auxiliary winch
- Rotation-resistant load line
- Heavy duty wood flatbeds
- Extra heavy duty wood flatbeds
- Extra heavy duty steel flatbeds
- Radio remote controls
- One-man or two-man baskets


- Self-leveling work platform
- Winch drum tensioner
- Continuous rotation
- Oil cooler
- Single front bumper outrigger
- (required for 370° or continuous rotation)
- Hydraulic hose reel
- Hydraulic auxiliary tool circuit
- Tool box





### **RS MODEL**

SPECIFICATIONS



### BOOM

30.5-100' (9.30-30.48 m) four-section full power fully synchronized boom. Patented keel boom design utilizes a keel shaped base plate combined with a deep, four plate boom section to optimize strength / rigidity-to-height ratio. Exclusive, patented color-coded boom and load charts allow the operator to easily determine boom extension, boom angle and load capacity. Maximum tip height with four-section 30.5-100' (9.30-30.48 m) boom is 110' (33.53 m). Maximum tip height with optional two-stage 30.5-55' (9.30-16.76 m) jib is 163' (49.68 m).

### WINCH

Hydraulic winch with 2-speed gear motor and planetary reduction gearing provides 2-speed operation. First layer rope pull is 15,000 lb (6 804 kg). Wire rope size is 5/8" (16 mm) with 45,400 lb (20 593 kg) breaking strength.

### **OPERATING SPEEDS**

Mainframe / turret assembly planetary gear rotation provides 180° rotation (370° with optional front bumper outrigger). Swing rotation is 75 seconds. Boom up/down is 60/41 seconds and boom extend/retract is 108/50 seconds.

### **HYDRAULICS**

Three-section pump allows the operator to perform simultaneous crane operations (winch, boom and swing). Capacities are 32, 17 and 8 gpm (122, 64 and 30 L/m). Hydraulic tank capacity is 90 gal (342 L). Hydraulic oil cooler is standard.

### CONTROLS

Fully proportional, excellent metering characteristics for precise boom movements. Independent outrigger controls allow the crane to be stable and level in rigorous working conditions. Load Moment Indication System has audio alarm and functional shut down when operator encounters an overload situation.

### **OUTRIGGERS**

- Front and Rear outriggers are Out & Down type. The maximum width over outrigger (Front and Rear) pads is 22' 4" (6.81 m).
- Front bumper outrigger is standard

### SUBFRAME

 Single fabricated, closed-box style subframe yields greater strength and rigidity. Wheelbase for standard truck crane mounting configuration is 261" (6.62 m).

### **OPTIONS AND ACCESSORIES**

- Single and two-stage jibs
- Multi-part load blocks
- Radio Remote Controls
- Enclosed Operators Cab
- Cab Heater
- Auxiliary winch
- Rotation-resistant load line
- One-man or two-man baskets
- Self-leveling work platform
- Winch drum tensioner
- Continuous rotation
- Hydraulic hose reel
- Hydraulic auxiliary tool circuit
- Tool box





### STINGER 70100 Contacts

### SALES

Tom Limbach Sales Director, Terex Cranes Office: (319) 352-9357 (815) 703-3905 Mobile: Office Fax: (319) 352-9395 Email. tom.limbach@terexwaverly.com

Diane Sheedy Director of International Sales Office: (319) 352-9326 (319) 352-9395 Office Fax: diane.sheedy@terexwaverly.com Email:

### **Bruce Kramer**

 
 Sales
 Manager, Terex
 Cranes

 Office:
 (319)
 352-9347

 Mobile:
 (815)
 703-3896

 Office Fax:
 (319)
 352-9395
 Email: bruce.kramer@terexwaverly.com

### **Chad Brandenburg**

Sales Coordinator, Terex Cranes Office: (319) 352-9356 Mobile: (910) 367-3152 Office Fax: (319) 352-9395 Empile Email: chad.brandenburg@terexwaverly.com

### **Angie Scribner**

Sales Assistant, Terex Cranes Office: (319) 352-9309 Office Fax: (319) 352-9395 Fmail<sup>.</sup> angie.scribner@terexwaverly.com

#### SERVICE - PARTS Roger Jones

 
 Notice
 Nanager
 Product Support

 Office:
 (910)
 395-8504

 Mobile:
 (910)
 367-6260

 Office Fax:
 (910)
 395-8538
 rjones@american-crane.com Email:

### **Dino Nelson**

Service Train	ning Specialist
Office:	(319) 352-9338
Mobile:	(815) 703-1800
Office Fax:	(319) 352-9378
Email:	dino.nelson@terexwaverly.com

Jim Chivers (Boom Trucks) Service Manager – Product Support Office: (319) 352-9352 Mobile: (815) 703-3901 Office Fax: (319) 352-9378 iim.chivers@terexwaverlv.com Email:

### Fred Backer (Boom Trucks)

Service Tech	inician
Office:	(319) 352-9388
Mobile:	(815) 703-6514
Office Fax:	(319) 352-9378
Email:	fred.backer@terexwaverly.com

Dan Kalkbrenner (RT &T Cranes) Service Manager - Product Support Office: (319) 352-9368 (815) 703-3900 Mobile Office Fax: (319) 352-9378 Email: dan.kalkbrenner@terexwaverly.com

### Jim Dawson (RT &T Cranes)

Service Manager - Product Support Office: (319) 352-9366 Mobile (815) 703-3899 (319) 352-9378 Office Fax: jim.dawson@terexwaverly.com Email:

### PARTS

Qualit

Office Mobile

Office

Email

Peggy Pellican Director of Aftermarket Sales (336) 644-0536 (336) 442-8348 (336) 644-0495 Office: Mobile Office Fax: Fax (801) 991-8193 ppellican@terexparts.com Email:

#### QUALITY ASSURANCE Lee L

inucikanip		
y Assu	rance Manager	
e.	(319) 352-9364	
e:	(815) 703-3898	
Fax:	(319) 352-9378	
:	lee.linderkamp@terexwaverly.com	

### **Clint Schrage**

Warranty Manager Office: (319) 352-9305 Office Fax: (319) 352-9378 Email: clint.schrage@terexwaverly.com

### ENGINEERING

George Green Director of Engineering Office: (319) 352-9315 Office Fax: (319) 352-9378 george.green@terexwaverly.com Email

#### **Dave Schoonover (Boom Trucks)**

Project Engineer Office: (319) 352-9372 Office Fax: (319) 352-9378 Email: dave.schoonover@terexwaverly.com

### Brian Thomas (RT Cranes) Project Engineer

Office: Office Fax: (319) 352-9386 (319) 352-9378 Email: brian.thomas@terexwaverly.com

### **Dave Frerking (T Cranes)**

Project Engineer Office: (319) 352-9321 Office: Office Fax: (319) 352-9378 Email: dave.frerking@terexwaverly.com

### MANAGEMENT

Dan Micheau 
 Operations Manager, Terex Cranes

 Office:
 (319) 352-9314

 Mobile:
 (815) 703 3903

 Office Fax:
 (319) 352-5727
 Email: dan.micheau@terexwaverly.com

**TEREX Cranes** 106-12th Street S.E. Waverly, IA 50677-9466 USA

TEL (319) 352-3920 FAX (319) 352-5727 EMAIL inquire@terexwaverly.com WEB terex.com

For more information, product demonstration, or detail on purchase, lease and rental plans, please contact your local Terex Crane dea We reserve the right to amend these specifications at anytime without notice. The only warranty applicable is our standard written warranty applicable to the particular product an sale. We make no other warranty, expressed or implied.

February 28, 2005



This information is for reference use only. Operators manual should be consulted and adhered to. Please contact Bigge Crane and Rigging Co. at 888-337-BIGGE or email info@bigge.com for further information.

BİGGE

A